







NOTES:

1. SHIPPED PARTIALLY ASSEMBLED WITH MALE XLR SUB-ASSEMBLY UNWIRED.

2. MATERIALS:

EXTENSION JAX ASSEMBLY: HOUSING & BUSHING - COPPER ALLOY, BRIGHT NICKEL INSULATOR - THERMOPLASTIC, NATURAL **INSULATING WASHER - PHENOLIC** TIP AND RING SPRINGS - SPECIAL COPPER ALLOY, POLISHED GROUND CLIP - SPECIAL COPPER ALLOY

MALE XLR SUB-ASSEMBLY: **INSERT - THERMOPLASTIC** SOLDER TERMINAL - SPECIAL COPPER ALLOY, TIN PLATED CONTACT PINS - SPECIAL COPPER ALLOY, SILVER PLATED SCREW - STAINLESS STEEL

ADAPTER HOUSING: HOUSING - ZINC ALLOY, BRIGHT NICKEL **TUBULAR INSULATOR - MYLAR** SCREWS - STEEL ALLOY, BRIGHT NICKEL

UNLESS OTHERWISE SPECIFIED 1. ALL DIMENSIONS IN INCHES - TWO PLACE DECIMALS ±0.02 - THREE PLACE DECIMALS ±0.005 А 26232 2-15-07 то TJK BY APVD REV ECO NUMBER DATE DO NOT SCALE DRAWING REVISIONS 4 SolidWorks CAD File B

 $\overline{\mathbf{T}}$